# ACCELERATOR INSTALLATION SAFETY SUPPORT - Strategy and lessons learned



2<sup>nd</sup> BrightnESS Best Practice Workshop – June 13 and 14



## **Recurrent Questions**

What are the Personal Protective Equipment required to be on site?

What documentation do I need to fill-in before starting installation activities?



Which kind of training do I need to follow before going on the site?

Who should I contact in case of an incident?

Who is responsible for the safety aspects during installation activities?

*Etc...* 



<u>Main objective of this presentation</u>: provide you with a better understanding of the prerequisites and instructions before and during installation activities







# Cryogenic buildings — Helium Compressor Building, Coldbox Building, Cryogenic Transfer Line


**Gallery** 


Pictures taken on 8th June 2017 **Helium Compressor Building Accelerator Cryoplant Hall Cryogenic Transfer Line Gallery Coldbox Building** 



# **Klystron Gallery and Test Stand 2**


#### Pictures taken on 8th June 2017





## **Accelerator Tunnel**


#### Pictures taken in May 2017



## **Accelerator Tunnel**



- Marking
- 2. Drilling
- 3. Installation of cooling piping, cable trays and Grounding bus bar
- 4. Installation of Racks (FEB level 090)
- Installation of Phase Reference Line
- 6. Installation of Ion Source
- 7. Installation of cables, RF waveguides in Stubs
- 8. Installation of Cooling skids (FEB level 100)
- 9. Commissioning of the Ion Source
- 10. Installation of RF distribution wall and Cryogenics Distribution System
- 11. Installation of Warm LINAC
- 12. Installation of Cryomodules and LWU's



#### Main challenges

30 consecutive months of installation

Several institutes and companies present on site

Concurrent commissioning and installation

Skanska Construction Site Rules

≈30-50 people at the same time estimated





## Involvement in the accelerator installation activities,

in collaboration with ES&H and Skanska

## **Today**



Support in the preparation of safety templates (e.g. WSCP, JHA, AHA)



Review of safety documentation (e.g. JHA, AHA, WSCP)



Participation to the pre-work visit
(System Leader, contractor representative, Area
Supervisor, Safety Team)



Coordination of safety training (e.g. BAS-U/P, safety harness, first-aid)







Support in the definition of control measures



Interface between AD, ES&H and Skanska



Participation to regular safety inspections on site







Preparation of online training courses

.....



## Work and Safety Coordination Plan (WSCP)

#### **GENERAL INFORMATION**



Duration of the

activity



Contractor information



Regulatory framework

### PREPATORY MEASURES




Pre-work visit



Organizational measures



Provision of services by ESS



- (Last/First Name, Company/institute) The ESS system leader is responsible for the distribution of this Work and Safety Coordination Plans to the signatories of this document;
   to the ESS Health and Safety Divisio
- The ESS system leader shall also archive this doc he contractor representative is responsible for the distribution of this Safety Coordin
- to the Health and Safety responsible of his company/institute;
   to his sub-contractors;
   to all other bodies that the company/institute must report to.

## ESS-0085649

#### **HAZARD IDENTIFICATION & CONTROL MEASURES**







Job Hazard Analysis (JHA)



Control documents

#### **INFORMATION AND TRAINING**







First aiders



Site map












Description of the installation work




Status: released on May 3<sup>rd</sup>, 2017



# Review and Approval of the safety documentation




## Good progress in the preparation of documentation






# **Accident/incident reporting templates**






## Area Hazard Analyses (G01, G02 & G04)



Training Purpose	HS site Induction	Site orientation training at gate	Safe lifting (slinging/rig ging)	Hot work training	Fall protection and rescue training (with harness)	High voltage Electrical awareness, ESA 14	(Scissor lift,	First Aid course (1 per working team)	Forklift truck training	Crane operator training for specific crane
Access to site	X									
Work on site (general)	X							X		
Access to site with vehicle/transport		X								
Performing hot work	X			X						
Performing lifting and coupling work	X		X							
Accessing energized areas, high voltage	X					X				
Working on MEWP	Χ				X		X			
Operating forklift	Χ								X	
Operating mobile crane, overhead crane, etc.	X		X							X
VALIDITY of courses (duration)	-	-	- (Swedish certificate)	5 years (Nordic certificate)	- (Swedish certificate)	3 years (Swedish certificate)	5 years (ISO 18878 certific ate)	3 years	Swedish BYN or TYA validation	Swedish BYN or TYA validation

# Safety trainings organized by AD in 2016/2017




# **Personal Protective Equipment (PPE)**





## **Installation Path**







Duy.Phan@esss.se

