

Experiences on Target/Instrument Installation at J-PARC

Masatoshi FUTAKAWA
J-PARC Center

CONTENTS

- 1.What is J-PARC/MLF**
- 2.Construction schedule**
- 3. Important facts through our experience**
 - 3.1 Settlement**
 - 3.2 Fire accident**
 - 3.3 Crane**
 - 3.4 Interface, Communication, Responsibility**
- 4. High lights of construction: Photos**
- 5. Summary**

CONTENTS

1.What is J-PARC/MLF

2.Construction schedule

3. Important facts through our experience

3.1 Settlement

3.2 Fire accident

3.3 Crane

3.4 Interface, Communication, Responsibility

4. High lights of construction: Photos

5. Summary

J-PARC

Japan Proton Accelerator
Research Complex

LINAC
400 MeV


Rapid Cycle Synchrotron
3 GeV, 25 Hz

Neutrino Experimental Facility

Main Ring
50 GeV

Materials & Life Science
Experimental Facility
(MLF)

Hadron Experimental Facility



JSNS 1MW spallation neutron source



Moderators



Cryogenic hydrogen system



Mercury target system

Proton beam
3 GeV, 1MW, 25 Hz

5m

Neutron beam lines (23)
19: operation 2:construction

-
- Diagram illustrating the cross-section of the JET (Joint European Torus) machine, showing the central column and surrounding shielding structure. Key components and dimensions are labeled:
- Dimensions:**
 - Overall height: 11600 mm
 - Overall diameter: $\phi 9540$
 - Internal height segments: 2400 mm, 1600 mm, 1520 mm, 2395 mm, 3100 mm
 - Internal diameter segments: $\phi 5000$, $\phi 9740$
 - Components:**
 - Seal Plate
 - Roof Shield
 - Shield Block
 - Iron Shield Block
 - Piping Pan Shield Block
 - Proton Beam Window Plug
 - Helium Vessel
 - Concrete
 - Reflector Plug
 - Hg-Target
 - Proton Beam Window
 - Proton Beam Line
 - Support Cylinder
 - Air Duct
 - Bottom Liner
 - Base Plate
 - Material Labels:**
 - Magnetite Concrete
 - Concrete
 - Other Labels:**
 - Outer Liner
 - B.L.
 - Target Trolley

Shielding around reflector

φ 9740

Outer liner in Helium Vessel




Section Through Shutters

- Magnetite concrete base for shutters.
- Flat top shutters.
- No shutter housing.
- No shutter support cylinder.

(duct: 300A pipe)

**Total Weight :
- 4600 tons**



Installation of Shutter




Installation of Target Station Shielding

Building Layout Overview

Building dimension :
Width : 70m
Length : 146m
Height : 30m
Exp. Hall Height : 22m

- Clear separation of the user area from the source components operation/ maintenance area
- Appropriate and effective facility layout considering components maintenance;
 - Hot-cell for handling highly irradiated components
 - High bay structure



Radiation shielding design criteria

- Dose rate at boundary of radiation controlled area: $< 12.5 \mu\text{Sv/h}$
- Dose rate at boundary of non-radiation controlled area: $< 0.25 \mu\text{Sv/h}$
- Dose under operating period $25 \mu\text{Sv/h}$



CONTENTS

1.What is J-PARC/MLF

2.Construction schedule

3. Important facts through our experience

3.1 Settlement

3.2 Fire accident


3.3 Crane

3.4 Interface, Communication, Responsibility


4. High lights of construction: Photos

5. Summary

J-PARC Construction Schedule



Construction Schedule in MLF



Readiness sheets for the first beam and user operation

① Checking point: 6 points

Criterion for judgment, Confirmation method, Documentation,
Until what time, Present status, Responsible person.

② Area: Total No. 20.

e.g. Building, Electric equipment, Mechanical equipment,
Air conditioning, Manipulator, Target system, Moderator
system, etc.

③ Components :Total No. 75

④ Item : Total No. 604

② 機器/大項目	詳細項目	主要判定基準	確認方法	文書番号	必要性	現状	担当
記載要領→	ビーム受け入れ前に確認すべき項目を記載。	具体的数値で判定できるものは、主要な値を記載。 できないものは、“NA”と記載。	確認できる文書名を記載。 まずは一般的な文書名で良いが、後々具体的な文書名に置き換えていく。	シート下部の参照文書リストと対応させる	完了時期 A: Day-1まで C: ~H20/9月運転 D: ~H20/12月運転 E: ~H21/3/E F: H21/4~	完了年月日記入 ・○:完了 ・△:条件付き完了(条件記載) ・■:未了(状況記載)	各項目の確認を責任を持って行なう担当者名を記載
③ 1. 水銀ターゲット容器							
1.1 各機能の確認	気密性能を有した構造であることを確認している。	耐圧試験: 0.625MPa 気密試験: 0.5MPa	完成図書(6522設備 水銀ターゲット容器) 2.5.2 検査成績書 水銀ターゲット容器の製作に関する技術報告(JAEA-Tech、執筆予定)	A-1 C-3	A	○	涌井
④	内圧による変形や水銀充填によるたわみを確認している。	変形: <1mm たわみ: <1mm	水銀ターゲット容器の構造強度解析設計報告(JAEA-Tech、執筆予定) 完成図書(6522設備 水銀ターゲット容器) 2.6.1 検査成績書 ターゲットシステム Off BC 報告書 1.水銀ターゲット容器(JAEA-Tech、執筆予定)	C-4 A-1 C-5	A	○	涌井




***Check on replacement procedure
according to readiness sheet***

Requirements to satisfy maintenance scenario

- Crane, Hatch, Floor load at High-bay etc. -


Moderator-reflector (M-R) maintenance scenario





***Check on replacement procedure
according to readiness sheet***

Target Replacement Scenario





CONTENTS


1. What is J-PARC/MLF
2. Construction schedule
3. Important facts through our experience
 - 3.1 Settlement
 - 3.2 Fire accident
 - 3.3 Crane
 - 3.4 Interface, Communication, Responsibility
4. High lights of construction: Photos
5. Summary

Results of settlement survey in 3NBT tunnel

Level survey in BT tunnel
from RCS to MLF




Result of the survey measurement (2)




The 3NBT tunnel, especially at the downstream, floated until January 2007. Then, it sank unit December, 2007. Even after the precise alignment in July, 2007, the downstream area in 3NBT slowly settles due to construction of neutrino beam line. Realignment would be necessary.

Results of settlement survey in the MLF


Position of piles for measurement



Measured result of Settlement



Relation of Settled value to Weight




- The MLF settled quickly during the MLF construction.
- After the completion of the construction, it settled slowly.
- After the completion of the installation of all the heavy neutron source components, it didn't almost settle.

Settled values are proportional to weights located in the MLF building. This proportional factor is about 0.3mm/1000t. In the future, the MLF building will settle to be 70 mm at the installation of all the neutron beam components.


Horizontal and vertical displacement of the experimental hall floor concrete

Horizontal displacement vectors of neutron beam line markers in the MLF experimental floor concrete



• Vector lengths were almost proportional to distances from neutron source center, it is thought that the concrete floor expanded thermally.

Uneven settlement of floor level in experimental hall in the period from Dec. 2006 to Oct, 2007



• 1st experimental hall floor sinks to 1.6 mm at maximum and 2nd one floats to 1.4 mm at maximum compared to the average value. The reason is that beam line shieldings at BL3, BL8 and BL10 are installed.

CONTENTS

1.What is J-PARC/MLF

2.Construction schedule

3. Important facts through our experience

3.1 Settlement

3.2 Fire accident


3.3 Crane

3.4 Interface, Communication, Responsibility


4. High lights of construction: Photos

5. Summary

Location of Fire in MLF building during construction



MLF building 1st Floor



Welding on piping at MLF

- 知識に乏しい者がTIG溶接をした。
 - 板間の隙間大きく、溶接棒を渡す無理な溶接を行い、溶接棒の熔解物が下方に落下した。
- TIG溶接は安全と過信し十分な養生をしていなかった。
 - 作業者は、溶接火花が出ないので耐熱シートの養生シートなしで行えると思った。
- 持場を離れる時の火気確認が不十分であった。
 - 11時50分に溶接作業を終え、作業終了後の溶接作業に伴う安全確認を行わずに、12時に昼食のため現場を離れた。



溶接現場写真：現場溶接箇所には耐熱シート養生無し

Fire of normal sheet by welding drop

- 平成19年2月22日12時10分、本溶接に直接関係のない別件の作業者が、気体廃棄物処理設備室前を通行時、異臭を感じ火災を発見した。
- 壁貫通仕舞いのSUS板溶接現場の溶接後の残り火が、床養生に引火し、発煙した。



気体廃棄物処理設備室の火災現場写真

CONTENTS

1.What is J-PARC/MLF

2.Construction schedule

3. Important facts through our experience

3.1 Settlement

3.2 Fire accident

3.3 Crane

3.4 Interface, Communication, Responsibility

4. High lights of construction: Photos

5. Summary

Busy construction and very busy in crane schedule

X No enough empty space for putting construction materials (shielding etc.)

X Construction period is very limited



2008




2009

2010

X Construction in narrow area


X Very busy in crane schedules



J-PARC MLF Experimental Hall (2011.1)




Statistical relation between proposal number and accident/incident number



Correlation between
No. of Proposals and
No. of accidents ?!

In the early stage period, most of the accidents are related to the neutron source, likely so-called early stage machine troubles.



Accidents in experimental halls


Year	Date of occurrence	Incident	Injured person. / Radio. Leak.	Operational mode when incident occurred
FY 2007	20-Dec	15t/5t crane , Wire rope rapture caused by incorrect 5t auxiliary crane operation to 8t shielding (BL20)	None	Maintenance
	22-Feb	7.5t Crane , Front Beam contact on wall (Experimental hall 2, Stairs wall)	None	Maintenance
	4-Mar	7.5t crane , Contact on the wall (Experimental hall 1, Stairs wall)	None	Maintenance
	6-Mar	7.5t, Scaffold on the crane girder contact air duct (Experimental hall 2)	None	Maintenance
	11-Mar	7.5t crane , Contact handrail on catwalk (Carry-in entrance at Experimental hall 2)	None	Maintenance
	25-Mar	30t crane , irregular winding caused by operation shaking hook when it is returned to the normal position. (BL14)	None	Maintenance
FY 2008		7.5t crane , Suspended load fall	None	Maintenance
	27-Jan	Hand, Laceration (Experiment preparation room 2)	Injured	User program
	24-Jan	Sample broken by high magnetic field, inappropriate treatment (BL10)	None	User program
FY 2009	31-Jan	PPS Alarm , failure (BL19)	None	User program
	16-Apr	Knee, Bleeding (Floor under vacuum chamber at BL01)	Injured	Maintenance
	5-Mar	Shin, bleeding (Front shielding of BL11)	Injured	Maintenance

Year	Date of occurrence	Incident	Injured person. / Radio. Leak.	Operational mode when incident occurred
FY 2010	14-Jul	Extension cable, short (BL02)	None	Maintenance
	13-Sep	Sample holder broken, Al hydride scatter in storage locker (BL21)	None	User program
	11-Mar 2011 EQ	Shielding (LiH) container broken and scatter (BL04)	None	Maintenance
FY 2011	12-Jul	15t/5t crane, Chain block break damage due to incipient failure (BL18)	None	Maintenance
	20-Jul	Staff, 50t crane, Suspended load contact on BL21 sheilding, Incorect setup. (Beamline shielding of BL20)	None	Maintenance
	30-Aug	50t crane, Shielding damage, Incorrect operation to bolted shielding (BL11)	None	Maintenance
	16-Sep	Lumbar, bone-fracture (Beamline shielding of BL19)	Injured	Maintenance
	5-Oct	7.5t crane, Contact on the wall (BL02)	None	Maintenance
FY 2012		Hand bleeding (BL21)	Injured	Maintenance
	27-Nov	Ejection of center stick of cryostat at BL14	None	User program
	5-Dec	Melting V beam window of furnace at BL20	None	User program
	10-Feb	Power strip, sandwiched between hatch and shielding (BL01)	None	User program
	6-Mar	Sample can damage at BL02	None	User program
	8-Mar	Sample splashing in SnI4 melting experiment at BL21	None	User program

Safety education & Training




Statistical relation between proposal number and accident/incident number



~~Correlation between
No. of Proposals and
No. of accidents ?!~~

Good !



CONTENTS

1.What is J-PARC/MLF

2.Construction schedule

3. Important facts through our experience

3.1 Settlement

3.2 Fire accident

3.3 Crane

3.4 Interface, Communication, Responsibility

4. High lights of construction: Photos

5. Summary

Interface, Communication, Responsibility

**Construction
Department**

**Materials & Life Science
Experimental Facility Group**

Interface

- **Responsibility** for building design and construction

**Requirements
Coordination**

- **Responsibility** for source components and instruments construction


- Width and height of building
- Load distribution on floor
- Pit location of neutron instruments
- Future expandability of instruments
- Beam design on the wall structure
- Embedded items
- Construction sequence

**Neutron Source
Design Core**

Interface

Instruments

**Requirements
Coordination**



CONTENTS

1.What is J-PARC/MLF

2.Construction schedule

3. Important facts through our experience

3.1 Settlement

3.2 Fire accident

3.3 Crane

3.4 Interface, Communication, Responsibility

4. High lights of construction: Photos

5. Summary



ヘリウムベッセル
2004年10月17日



アウターライナーを囲むSC壁
2004年12月16日




2005年11月30日



沈下測量作業
2005年4月23日

2006 Materials Life science Facility (MLF,JSNS) building in 2006





特性試験装置コリメーター設置

2007年3月15日

View in MLF


2011 Jan 7 (9 inst. oper. + 6 under const.)



Hall #1



BL08 & 09



Hall #2



BL18 & 19



Summary

- **Safety !**

- **Communication !**

In particular relating to interface among components.

- **Responsibility !**

Who is a person for each component and structure.

- **Special items to take care !**

Ground subsidence

Cran accidents

Fire, etc.