

LHC Installation

S. Chemli – Alignment, Coordination and Engineering Group

Acknowledgements to : P. Bonnal, J. Coupard, D. Duret, L. Evans, P. Faugeras, K. Foraz,
C. Hauviller, P. Proudlock, R. Saban, R. Schmidt



ENGINEERING
DEPARTMENT

Main topics exposed


- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management

Main topics exposed

- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management

The LHC Project timeline

84: First studies of the LHC project



94: Approval of the project by the CERN Council

98: DUP & Start of civil engineering




08: 1st beam

09: Start of Physics


13-14: Long shutdown 1

19-20: Long shutdown 2

24-25: Long shutdown 3



First LHC beams




LHC Project as a Mega Project

Mega Project factors	Impact on the project
Time Horizon <ul style="list-style-type: none">• Multi-year• Multi-phase	Risks had to be properly analysed
Chain of Command <ul style="list-style-type: none">• Multi-layer organization• Matrix Structure	Responsibilities had to be clear
High-degree of Specialisation <ul style="list-style-type: none">• Subject Matter Expertise• Cutting-Edge Technology	Coordination was crucial
Dispersed Teams <ul style="list-style-type: none">• Virtual teams in multiple locations• Outsourcing to other countries	As well as clear and transparent communication


Main topics exposed

- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management

LHC Project Organization (2004)



IC group organization



LHC installation history

8 sectors considered as 8 machines

- Civil engineering and LEP dismantling
- General Services
- Cryogenics
- Machine
- Hardware Commissioning



Installation

Studies & Integration

Civil Engineering phase

- 4 main contracts to build:
 - Surface buildings: modification & construction
 - Underground
 - 2 injection tunnels ~5km
 - 2 ejection tunnels ~2km
 - 2 new experimental areas
 - Modification & consolidation of existing areas

240'000 m³



T
I
2




D
U
M
P



C
M
S



A
T
L
A
S



Civil Engineering phase

- Main issues encountered

- From the Civil Engineering side

- Modification of the contract envelop
 - Introduction of the 35 hours/week law in France
 - Impact on resources and schedule
 - Long discussions leading to the introduction of a fixed cost mechanism
 - First time CERN had outsourced the design and the work supervision to external consultant firms

- From the Coordination side

- Dust
 - Endless end !



General Services installation

- Cabling & general electrical devices

- More than 4'500 km of installed cables
- 2 Industrial services contracts




- Main problems encountered

- On the Electrical Service side
 - 3D integration not complete before the start of the installation, and late requests from end-users
 - Availability of cables (another contract)
- On the Coordination side
 - Lots of delays
 - Non-Conformities at the end of the works



General Services installation

- Optical fibres
 - Qualified contractor, very good follow-up
 - Fast installation
- Water cooled-cables
 - Unreliable schedule
 - Technical problems
 - Mechanical aspects under-estimated
 - A technical CERN «rescue» team set in place to solve the issues



General Services installation

- Cooling & Ventilation

- 160km primary cooling pipes & ~8km of flexibles
- Systems installed
 - in surface buildings & experimental areas,
 - in electrical alcoves,
 - modification of the control system



- Main problems encountered

- Nominal progress rate achieved from the 4th sector (/8)
- Installation drawing not verified by the 3D integration team



Cryogenic installation

- Cryogenic islands

- Several contracts
- 5 islands for the 8 sectors
- Modification and new installation
- «Isolated» works – went smoothly



- Cryogenic line installation

- 1 contract for the 27km
- Started in June 03
- After several months of serious technical and schedule problems, works were stopped by the enterprise on July 04
- In order to progress with the installation , CERN set up another technical «rescue» team to repair and reinstall the faulty equipment already at CERN
- Works resumed on November 04, ended in December 06



Impact of the delay of the cryogenic line

- Risks

- QRL systematic tests at cold cancelled
- Pilot sector on Beam 2 Injection cancelled

- Logistics

- Cryo-magnets storage

- Coordination

- Sequence of sectors changed
- Time-window dedicated to the machine installation reduced
- Time-window dedicated to the test phase reduced by a factor 2
- Search for additional human resources for the Hardware Commissioning



Cryo-magnet transport


- 95% of the total number of cryo-magnets lowered down through one single pit
 - Weight (34t) / load capacity of the crane
 - Dimensions: length ~17m
- More than 1'700 cryo-magnets transported at a speed of 3km/h max
- Huge scheduling constraint
- Main problems encountered
 - Crossing other worksites in narrow areas



Cryo-magnet interconnections


- Including more than 1'900 interconnections, vacuum tests, electrical tests
- Slow start due to missing adjacent magnets and co-activities
- Cruising speed reached at the 3rd sector

10'000 induction brazes
60'000 ultrasonic welds



Cryo-magnet interconnections

- Main problems encountered
 - Nov. 06- the inner triplets crisis: defect on the exchanger tube
 - Few weeks after their repair: the spiders broke
 - «Task Force» set up to repair and analyse the design
 - First sector cool-down without Inner Triplets in order to gain experience for the following phases
- Sept. 07: during the warm-up of the 1st sector for the IT connection, a certain number of PIMs (Plug-In Modules) were broken
 - «RF balls» built to diagnose the number of faulty PIMs



Individual system tests

- Each system was individually tested
 - Power converters and associated equipment
 - Pressure and leak tests of the cryogenic line
 - Collimator tests
 - Interlock system tests
 - Extraction energy system tests
 - Beam Instrumentation tests
 - Ejection and dump systems tests
 - Leak and pressure tests of the continuous cryostat
 -
- Electrical Quality Assurance testing for the arcs and the individually powered magnets

Cool-down

- January 07: difficult start, but weak points quickly identified and compensatory measures set up:
 - On Cryogenics side
 - tuning of Cold compressors
 - tuning of magnets instrumentation
 - condensation and frost on the Current Leads
 - On General Services side
 - electrical cuts
 - network issues
 - tuning of the primary cooling



Hardware Commissioning & Powering tests




- Started in March 2007, difficult start due to a low «Mean Time Before Failure» and a high «Mean Time Before Recovery» !
- March 2008: with respect to the last delays and in order to comply with our commitments to have beam before summer, decision was taken to qualify all circuits to 5TeV (7TeV nominal)



2008, September 10th

First beams

Beam 1 threaded around the machine in 1h
Beam 2 threaded around the machine in 1h30



2008 incident


- On 19 September 2008, during powering tests, an electrical fault occurred producing an electrical arc and resulting in mechanical and electrical damage, release of helium from the magnet cold mass and contamination of the insulation and beam vacuum enclosures.



2008 incident

- In the days following the incident which occurred in sector 3-4 of the LHC, a **Task Force was set up using experts from the relevant LHC systems to:**
 - establish the sequence of facts, based on experimental observations and measurements
 - analyse and explain the development of events, in relation to design assumptions, manufacturing and test data and risk analyses performed
 - recommend preventive and corrective actions for Sector 3-4 and others.
- A fantastic and massive support CERN-wide!

The LHC repairs in detail



Lessons learned – on installation

- Maintaining **sufficient resources** in the home laboratory is necessary to cope with
 - tasks outside the interest and capabilities of industry
 - unexpected technical or commercial difficulties
- The **flexibility** and the **commitment** of our colleagues were the key competencies leading to success
- But **freeze** the layout of the machine as soon as you can, it will help a lot...
- **Balance risks**: lack of competition for contracts can increase project costs and affect deadlines
 - 2 firms at least for a single adjudication on large/main contracts
 - the only times it was not done, it led to problems (2 out of 3)

Nota Bene
Hardware only
No Software
No Controls

Main topics exposed

- Some words of introduction
- The LHC installation from the inside
 - Organization
 - Installation phases
 - Lessons learned on the installation
- Behind the scenes
 - Methodology
 - Lessons learned on project management

Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle

Quality Assurance

CERN
CH-1211 Geneva 23
Switzerland



LHC Project Document No.
LHC-PM-QA-100.00 rev 1.4

CERN Div./Group or Supplier/Contractor Document No.

AC/DI/PEF

EDMS Document No.
103544


Date: 2003-04-02

Quality Assurance Policy

QUALITY ASSURANCE POLICY AND PROJECT ORGANISATION

Table of Contents

1. PURPOSE	5
2. SCOPE	5
3. QUALITY ASSURANCE POLICY	5
4. ORGANISATION	6
4.1 PROJECT ORGANISATION	6
4.2 LHC PROJECT LEADER	6
4.2.1 LHC PROJECT MANAGEMENT AND PROJECT LEADER'S OFFICE	6
4.2.2 SUPPORTING DIVISIONS	7
4.2.3 COMMITTEE STRUCTURE	8
4.3 QUALITY ASSURANCE ORGANISATION	9
4.3.1 RESPONSIBILITIES	9
4.3.2 DEPUTY TO LHC PROJECT LEADER FOR QUALITY ASSURANCE	9
4.3.3 QUALITY ASSURANCE REPRESENTATIVES AND QA WORKING GROUP	9
5. QUALITY ASSURANCE PLAN	10
5.1 PROJECT DEFINITION	10
5.1.1 PARAMETERS AND LAYOUTS	10
5.1.2 LHC HARDWARE BASELINE	10
5.1.3 CONFIGURATION MANAGEMENT	10
5.2 DESIGN CONTROL	11
5.3 DOCUMENT AND DATA CONTROL	11
5.4 PURCHASING AND CONTRACTING	11
5.5 PRODUCT IDENTIFICATION AND TRACEABILITY	11
5.6 MANUFACTURING PROCESS CONTROL	12
5.7 INSPECTION, TESTING AND QUALITY RECORDS	12
5.8 CONTROL OF NON-CONFORMING PRODUCT	12
5.9 HANDLING, STORAGE, PACKING AND DELIVERY	12
5.10 INSTALLATION, OPERATION AND SERVICING	12
5.11 QUALITY AUDITS	13
5.12 TRAINING	13
6. SAFETY POLICY	13
6.1 GENERAL SAFETY	14
6.2 QAP FOR IMPORTANT SAFETY ELEMENTS	14
7. ANNEXES	14
8. REFERENCES	15




'I say what I'll do and I do what I said'

Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle
to ensure that all stakeholders are
using the same processes




Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle

to ensure that all stakeholders are
using the same processes



- Configuration Management & 3D Integration


what | Hardware Baseline (aka Product Breakdown Structure)

where | Layout Database for Functional Positions – fully developed during the project times
| 3D Integration fed with the Digital Mock-Up – from Layout DB to 3D-CAD systems

Project/Product Breakdown

The responsibility of the Project Engineers is reflected by the organization in subprojects

A set of approved and released documents that represents the definition of a product at a specific point in time



The configuration is mirrored in a tree structure where all the documentation is contained

The LHC – understood as a project or a facility – is decomposed in terms of functions


- systems
- sub-systems
- main type units to be manufactured

Configuration Items fully under the control of the configuration management and on which the impact of the changes is analysed

Courtesy R. Saban

All of these documents are stored in EDMS and/or CAD PDM

With the exception of mails and scientific publications



Courtesy P. Bonnal – see openSE.web.cern.ch

Methodology (1/3)

- Quality Assurance Plan


Covers documentation and processes over the lifecycle



to ensure that all stakeholders are
using the same processes


- Configuration Management & 3D Integration


Hardware Baseline (aka Product Breakdown Structure)


Layout Database for Functional Positions – fully developed during the project times
3D Integration fed with the Digital Mock-Up – from Layout DB to 3D-CAD systems













LayoutDB | GIS portal

Methodology (1/3)

- Quality Assurance Plan

Covers documentation and processes over the lifecycle

to ensure that all stakeholders are using the same processes





- Configuration Management & 3D Integration

Hardware Baseline (aka Product Breakdown Structure)

Layout Database for Functional Positions – fully developed during the project times

3D Integration fed with the Digital Mock-Up – from Layout DB to 3D-CAD systems

to ensure that all stakeholders are working on the same version of the specifications
to represent the accelerator in 3D in an automated way



Methodology (2/3)

- Manufacturing and Installation


Manufacturing follow-up from the early stages

Equipment delivery dates monitoring in the LSS –

Design Office and Central Manufacturing facility scheduling



Assembly Tree




Equipment Folder: Properties

Equipment Identifier: HCMCSMH001-KE001226
Other Identifier: MCS-MA-11226
Description: MCS Magnet Assembly (A2)

Main Made of Equipment data Manufacturing Operation Documents History Map			
Actions : History			
External Links			
Click here to view data on the external database			
Property Values			
Property	Nominal Value	Value	Unit
Drawing Version		1	
Protection Resistor ID		MCS-PR-BOO1	
Shield Body ID		MCS-ES-11332	
Shield End Cap ID		MCS-EC-11333	
Connection Cover Plate ID			
I leak (4K)		0.21	µA
R dc (4K)		55.69	nohm
I leak (300K)		0.1	µA
R dc (300K)		0.102	ohm
Quench Current 1		1094.37	
Quench Current 2		1160.71	
Quench Current 3		1159.76	
Quench Current 4		1159.93	
Quench Current 5		1159.02	
Quench Current 6			

Monitoring of delivery dates in the LSS

- Late design – hence late manufacturing – on some equipment



- Clear influence on the order of the sectors to close and to bake-out
- Manufacturing of replacement chambers in some cases

Methodology (2/3)

- Manufacturing and Installation


Manufacturing follow-up from the early stages

Equipment delivery dates monitoring in the LSS –

Design Office and Central Manufacturing facility scheduling

to trace all the important assets with their test results

to organise the order of vacuum sub-sectors to close and the bake-out activities



Methodology (2/3)

- Manufacturing and Installation


Manufacturing follow-up from the early stages

Equipment delivery dates monitoring in the LSS –

Design Office and Central Manufacturing facility scheduling

to trace all the important assets with their test results

to organise the order of vacuum sub-sectors to close and the bake-out activities



- Coordination meetings

Configuration, Integration, Planning,

Worksite follow-up & logistics – Hundreds of ad-hoc meetings


Analysis of co-activities and worksite safety organisation

Safety

- Safety is **1st** priority
- Delicate balance between host states & European & internal rules
- Description of the frame work of any worksite is mandatory
 - “Plan de Coordination des Travaux et de la Sécurité” applicable organizational measures in matter of work planning and coordination, of general safety and radiation protection
- Additional procedures are edited to take into account our specific risks



SAFETY



CERN/TIS-GS/98-10
PGCSPS
LHC-PM-IP-0001

Work of contractors on the CERN sites
Safety regulations applicable to the work of contractors at CERN

TISGS98.pdf

IS 5 Rev. Emergency stops
IS 7 Rev. Individual protection
IS 22 Rev. Rules for the safe use of
IS 23 Rev.2 Criteria for the selection of
cables and equipment for
fire safety and radiation
IS 24 Regulations applicable
installations
IS 25 Beryllium
IS 26 Electrical test bays
IS 27 Electronics laboratories
IS 28 Dangers due to electric
IS 32 Polychlorinated biphenyls
IS 33 Voltage domains according
IS 34 Glass windows
IS 36 Rev. Safety rules for the use
magnetic fields at CERN

A2 Rev. Reporting of accidents
A3 Rev. Safety colours and safety
A4 Rev. Confined spaces
A5 Safety of Experimental
A6 The two-person rule of
A7 Road traffic at CERN
A8 Protection against noise
B Chemical safety code

CERN
CH1211 Genève 23
Suisse



RP ECRS 978710 REV. 0.2 VALIDITE Draft

REFERENCE
CERN-BE-Note-2009-008-ASR

Date : 2009-02-18

NOTE D'ORGANISATION

PLAN DE COORDINATION DES TRAVAUX ET DE LA SÉCURITÉ DE L'ACCÉLÉRATEUR LHC 2008-9 WORK AND SAFETY COORDINATION PLAN OF THE LHC ACCELERATOR 2008-9

Résumé Abstract
Ce document s'adresse à toutes les personnes amenées à intervenir sur les installations de l'accélérateur LHC, qu'il s'agisse de personnels CERN (titulaires et utilisateurs) ou d'entreprises contractantes. Ce document adresse à toutes les personnes susceptibles d'intervenir sur l'accélérateur LHC, que ce soit des membres du personnel CERN (titulaires et utilisateurs) ou des entreprises contractantes. Ce document fournit une information succincte sur les règles de planification et de coordination de la sécurité générale.



CERN
CH-1211 Geneva 23
Switzerland
The Large Hadron Collider project

LHC Project Document No.
LHC-D-ES-0008 rev 1.0
CERN Document No.
EN-MEF,TE-MPE,TE-CRG,TE-EPC,BE-OP
1109116
Date: 2010-11-29

Engineering Specification

ELECTRICAL SAFETY FOR INTERVENTIONS ON, OR CLOSE TO SUPERCONDUCTING CIRCUITS DURING 2010-2011 XMAS BREAK

CERN
CH1211 Genève 23
Suisse



EDMS NO. 1110268 REV. 0.1 permanent

REFERENCE
LHC-OP-OSP-0023 v 0.1

Date : 2010-12-29

PROCEDURE

Access to the underground areas of point 7 and arcs 67-78 of LHC during the ODH and Fire central displacement at point 7

ABSTRACT

This document describes the procedure to grant access to personnel for urgent interventions in the underground areas of LHC point 7 and arcs 67 and 78 during the ODH and Fire central displacement at point 7.

\$37.pdf

\$38.pdf

\$39.pdf

\$39_A1.pdf

\$40.pdf

\$41.pdf


\$42.pdf

\$43.pdf

\$44.pdf

\$45.pdf

- Operational schedules



Methodology (2/3)

- Manufacturing and Installation



Manufacturing follow-up from the early stages

Equipment delivery dates monitoring in the LSS –

Design Office and Central Manufacturing facility scheduling

to trace all the important assets with their test results

to organise the order of vacuum sub-sectors to close and the bake-out activities



- Coordination meetings

Configuration, Integration, Planning,

Worksite follow-up & logistics – Hundreds of ad-hoc meetings

Analysis of co-activities and worksite safety organisation

to keep all stakeholders on the same page and to reduce risk due to co-activities

Methodology (3/3)

- Deviation Handling

Changes are reported and approved – or not – by the Committees

Non-conformity reports on equipment and installation

Change Control

- Configuration baselines are established whenever it is necessary to define a **reference** configuration during the lifecycle of the product.
 - during project times, this was mainly driven by optics modifications or by heavy changes in the project (RF modifications, collimation project major review, etc.)
 - the baseline is used as a starting point for further activities until it is revised in a controlled way.
- All **changes** are **reported** to the Committees handling the project or the facility as soon as they get circulated
 - **approval** of Change Requests is done by the Committees,
 - other technical documents are mentioned at the start of the approval cycle and when released
- Between two baselines, all of the impacted documents are listed in **Release Notes** (also in EDMS)


Deviations handling

- From the nominal definition, deviations are treated in terms of documentation by
 - a simple update of the Engineering Specification of a product as long as there is no impact outside (e.g. updates on the list of cryo-dipoles types due to a new set of interconnections)
 - an Engineering Change Request issued by any of the stakeholders of the project (and having an impact on the Form-Fit-Function of a product) if some parameters/design need to be modified
 - or a Non-Conformity Report on an equipment or its installation (deviation from nominal positioning) – that forces the update of the Engineering Specification of the product
 - **equipment** non-conformities are traced within the Manufacturing and Testing Folder (MTF – Infor EAM). If the non-conformity is impacting other equipment an ECR could be generated.
 - **installation** non-conformities are often detected by 3D scans superimposed to the 3D-integration model

All stored in EDMS

Installation non-conformities

- Is there enough space left after each installation stage?
 - 3D geo-referenced scans on the top of the 3D mock-up scenes
 - Installation non-conformities (~500 in total) treated by the Integration team and consequent modifications – if needed – done by the responsible teams



Methodology (3/3)


- Deviation Handling

Changes are reported and approved – or not – by the Committees

Non-conformity reports on equipment and installation

to trace the nominal machine and deviations

to trace the space left for the coming equipment installation



Methodology (3/3)


- Deviation Handling

Changes are reported and approved – or not – by the Committees

Non-conformity reports on equipment and installation

to trace the nominal machine and deviations

to trace the space left for the coming equipment installation




- Reports

Earned Value Management set up – see back-up slides

Periodic reports to the Top Management, the Project Leader Office, the Committees

Scheduling reporting




Example of IC-group direct reporting to the DG on a every month basis

Broken line

Yellow line is today

Black line is "today's broken line"

Red line is "last month's broken line"



Methodology (3/3)


- Deviation Handling

Changes are reported and approved – or not – by the Committees

Non-conformity reports on equipment and installation

to trace the nominal machine and deviations

to trace the space left for the coming equipment installation



- Reports

Earned Value Management set up

Periodic reports to the Top Management, the Project Leader Office, the Committees


to trace deviations on schedule/cost and to take corrective actions to keep the project on tracks

Lessons learned – on project management

- Achieving **quality** throughout the project involves the establishment and enforcement of a **comprehensive** and **solid** QAP
 - all stakeholders **adhered** to the message 'I say what I'll do and I do what I said'
 - the **weak** point was the Interface Specification between two Work Packages
- **Unique** methodology and common Project Management **culture**
 - methodology now in place for all new CERN projects (Elena, HIE-Isolde, LIU, HL-LHC, Awake, Physics Beyond Colliders,...) – **scalability**
 - 150 Project Engineers in the Accelerator Sector now trained with **OpenSE**
- **Granularity** on information and expectation levels was properly set
 - at the crossing points of different points of view, **installation oriented**
- Project **investment** on people and tools – learning curve
- EVM should be carefully introduced, supported and assisted.
 - done in the middle of the project, but allowed to restore member states confidence

Lessons learned – on project management


- **Central** organisation: A **dedicated** group was put in place gathering the key organisers
integration, configuration, coordination and scheduling, logistics, operational safety, hardware commissioning
- **Small** teams per topic
 - configuration – 6
 - integration – 6
 - scheduling – 3
 - logistics – 1
 - operational safety – 4+2
 - hardware commissioning – 2+10
 - site management – 8
 - transport – 10+30
 - assistance to installation – 3+10



Corresponding **tools** and **services** were handled **centrally** for all the groups (equipment and service groups)

Conclusions

- A **solid & common methodology** of project management is crucial
 - openSE is becoming CERN-internals standard in the Accelerator Sector
- **Our best resources are human resources:** in addition to a **strong expertise, flexibility, accountability and communication** shall not be forgotten



Source: ©2013 Project Management Institute, Inc. *Pulse of the Profession In-Depth Report: The High Cost of Low Performance: The Essential Role of Communications*, May 2013. PMI.org/Pulse

Back-Up slides

Personal Lessons Learned
Configuration Management,
From Project to Programmed Stops,
Parallel configuration of facilities (LHC – Injectors) and projects (LIU – HL)
IMPACT
PLAN
openSE




ENGINEERING
DEPARTMENT

Lessons learned - personal

- To get documents of high quality means to invest **time and effort** in reading/correcting/suggesting to authors
 - essential to keep 100% control on the baseline documents and not delegate
 - added value is to identify impacted stakeholders not mentioned by authors
- Mid-term/**long-term** personnel to handle the configuration and integration data is essential
 - the learning curve is **long** – diversity of document types, equipment groups, needs, ... - current exercise is over 2 years
 - **interactions** with Digital Mock-Up, Integration and Scheduling are important to master
- Better **3D reviewing** sessions with all players
- **Flexibility** and **human interactions** are essential ingredients of success
- Non-conformity checking is better **accepted** in team-work mode

Configuration Management




Configuration Management

A set of approved and released documents that represents the definition of a product at a specific point in time

The LHC – understood as a project or a facility – is decomposed in terms of functions

- systems
- sub-systems
- main type units to be manufactured

one-to-one mapping
one-to-many mapping



BOM management

- assemblies
- sub-assemblies
- parts

This is mainly how reflected in CAD, PDM-PLM, EAM systems. Breakdown of types


mainly information
(3D mock-ups, 2D drawings,
BOMs, various documents)

physical assets
and associated documents

Purchasing documentation in PBS



PURCHASING-CONTRACTING



CERN/FC/5164-I
CERN/FC/5164-II

General Conditions Governing Invitations to Tender and Tenders
General Conditions of CERN Contracts

FC5164-I.pdf
FC5164-II.pdf

OTHER PURCHASING DOCUMENTS

CERN/FI-A/2753

Certificate of property
Bank Guarantee

CertProp.pdf
FI2753.pdf

WORK OF CONTRACTORS ON THE CERN SITES

CERN/ FI/ 120

CERN/ FI /98
CERN/DSU-DO/RH/9335

TIS/ES/MD/rb/89-423
DSU-DO/RH/1845
CERN/DSU-DO/RH/8200
DSU-DO/RH/6833

Special conditions for the operation and/ or maintenance of CERN equipment and installations

Special Conditions for the provision of temporary labour to CERN
Relations between CERN, the competent bodies of the Host States and contractors concerning occupational health and safety on the Organization's site
Special Health and Safety Committee
Contractors & their staff: Access to & activities on the CERN site
The Tunnel linking the CERN sites - Rules for use
Conditions governing the use of vehicles belonging to or hired by CERN by the personnel of CERN contractors

FI120.pdf

FI98.pdf
DSU9335.pdf

TIS89-423.pdf
DSU1845.pdf
DSU8200.pdf
DSU6833.pdf

DIR/ADM/MI-RH/660

Regulations for use of storage areas in the CERN site for contractor's equipment
Position of non- French firms setting up an establishment in France and of their staff
Position of Non-French firms seconding staff to France without setting up an establishment there

ADM660.pdf
FR001.pdf
FR002.pdf

CERN/DSU-DO/RH/8917/Rev.1

Information concerning residence and work permits for employees of CERN contractors

DSU8917.pdf

Procédure de demandes d'autorisation de travail pour frontalier applicable aux employés d'entreprises établies en Suisse, liées au CERN par un contrat

G010425.pdf

Memorandum relating to conditions governing the provision of services in France by firms established abroad (extract)

DSU11048.pdf

Letter from French Inspector of Labour (referenced in above memorandum)

F020731.pdf

USE OF CERN FACILITIES

Operational Circular N° 5

Use of CERN Computing Facilities


OC5.pdf

Introduction




- Versioning of Accelerators in Operation is sequential
 - Based on TS/(e)YETS/LS
 - One snapshot in the timeline for each TS to freeze the configuration
- Preparing projects in advance requires forking the configuration on
 - Hardware Baselines – time-dependent and forked
 - Layout data – time-dependent and forked
 - Integration Scenes – with all the services included – time-dependent and forked
 - List of Activities to prepare for the new configuration – naturally time-dependent and forked

Machine Configurations




- Configuration of the Facilities in operation are managed by a Committee
 - Based on TS/(e)YETS/LS

Machine Configurations



- Configuration of the Facilities in operation are managed by a Committee
 - Based on TS/(e)YETS/LS
- Machine Configuration is reporting to the Committees
 - Regular presentations on the coordination of the activities
 - Validation of the Change Requests
 - Integration is embedded in the Change Requests
 - Layout is maintained


Machine Configurations



- Configuration of the Facilities in operation are managed by a Committee

- Machine Configuration is reporting to the Committees
 - A preparation time with Eng. Specifications and Change Requests circulating and getting approved
 - Regular presentations on the coordination of the activities
 - A review and validation time of coherence
 - Validation of the Change Requests
 - An implementation time
 - Integration is embedded in the Change Requests
 - A validity for a Run
 - Layout is maintained


Machine Configurations



- A given Configuration has sometimes need to be known in advance
 - A preparation time with Eng. Specifications and Change Requests circulating and getting approved
 - Equipment planned for 2018 and ECR already approved
 - A review and validation time of coherence
 - Projects planned and on time – need their configuration stored and handled
 - A validity for a run


Preparing configuration is heavily linked to the equipment lifecycle

Equipment Lifecycle



- ACE sections to perform simulations on
 - Scheduling – enough time for the activity
 - Integration – enough space
 - Configuration – any other request in the neighborhood

Equipment Lifecycle



Once the study phase is over:



- **Scheduling** - update the following period of time
- **Configuration** - close documentation
- **Integration** - confirm space, utilities, reservation safety files
- **Configuration** - documentation
- **Integration** - update machine drawing layouts

Changes in the tools – EDMS

- Configuration documentation in EDMS needed to be changed to allow an easy forking on structures.
 - Structures needed to be separated
 - Documents need their validity to be re-affirmed for a given configuration
 - E.g. specifications on the QRL sectorisation remaining valid up-to configuration Run 2021 or Run 2022.
 - E.g. removal of the String 2 documentation in current and future baselines.


Changes in the tools – EDMS

- Refurbishment of the EDMS portal to reflect the forking of the structures and to follow the Engineering Lifecycle
 - Studies – Projects – Operation – Dismantling
 - Allows a better view on the baseline forking



Changes in the tools – EDMS

- Refurbishment of the EDMS portal to reflect the forking of the structures and to follow the Engineering Lifecycle
 - Studies – Projects – Operation – Dismantling
 - Allows a better view on the baseline forking




Changes in the tools – Layout Drawings

- There is an on-going campaign by ACE-INT
 - to identify and produce all the missing layout drawings, based on machine regions (period, sector, section)
 - to separate all-in-one (e.g. LT, LTB, LBE, LBS) to individually manage them
 - to clarify any confusion with the assembly drawings produced by EN-MME Design Office which are mechanical and not layout drawings
- This set of drawings will then be used to produce the layout drawings for the post-LS2 period
 - in parallel to the data entering in the layout database
 - knowing that all incremental changes drawings have already been produced for the ECRs.

Changes in the tools – Project Versioning


- Sequential versions for the HL-LHC project (optics versions 1.1, 1.2, 1.3, etc.) will have to be tagged in the new layout database on the base of the Configuration for Run 2026.
 - This will allow a coherence check per recorded optics version
 - NB: The current version of the database is unable to do this

- As the LIU project is close to implementation, data will be introduced based on:
 - Runs 2017 and 2018 configurations (EDMS and partially Layout) for the pre-LS2 version
 - Run 2021 configuration for the post-LS2 version (EDMS and Layout)



Changes in the tools – Layout DB

- New layout DB (+ WEB GUI) under development by BE-CO



- What is a version in the new Layout DB ?
 - A version represents an installed layout at the end of a stop period
 - It is valid for the whole following run period

From project to installation



Functional and Engineering Specifications

- to make people describe their requirements, their interfaces, their engineering

Engineering Change Request/Order

- to ensure the information is up-to-date at a given time, and shared with all those participating to the project
- to control changes through validation and update impacted specifications

CDR(Conceptual Design Report), TDR (Technical Design Reports), Schematics, 2D-Drawings, 3D-Mockups, Technical Notes, Technical Reports, Technical Datasheets, various lists, BoMs , Procurement Documents (TD,TQ, QC, TS, TF), Scientific Publications, illustrations, sketches, photos, videos

The installed collider



The installed machine evolves

- Components are exchanged
- New components are installed
- The configuration changes

Engineering
Change
Request/Order




- Changes are documented
- The impact on safety, infrastructures, on neighboring systems, planning, budget is carefully studied
- The layout is updated to ensure the integration of the next changes is possible

Courtesy R. Saban

The Master Schedule



Review of the **strategic** goals and major milestones



LHC construction & installation schedule

From strategy to tactics


- Aim: implement and control the flow of installation
- Respect the main milestones of the Main Schedule
- Based on the WBS
- Linear schedule




Detailed schedules

From tactics to operation

- The LHC main ring: 8 sectors treated as 8 identical machines
 - Arcs
 - Long Straight Sections
 - Services areas



- 3 main MSProject files
- Review of the 3 schedules, and their dependencies on a weekly base



Baseline evolution



LHC civil engineering work



Water cooled cables





Cryogenic line




1st LHC cryo-magnet lowering



LHC Interconnection work



Baseline schedule



The delay of the QRL imposed the reshuffling of some activities. Additional resources were added for the following phases **+3 months**

Major non-conformities during installation: **+2 months** because of the QRL, **+4 months** because of the interconnections


Id	Title	Created on
LHC-PM-MS-0005 v.4.0	LHC Construction/Installation General Coordination Schedule	2007-06-14
LHC-PM-MS-0005 v.3.1	LHC Construction/Installation General Coordination Schedule	2006-10-10
LHC-PM-MS-0005 v.3.0	LHC Construction/Installation General Coordination Schedule	2006-07-07
LHC-PM-MS-0005 v.2.0	LHC Construction/Installation General Coordination Schedule	2005-04-06
LHC-PM-MS-0005 v.1.7	LHC Construction/Installation General Coordination Schedule	2003-03-31
LHC-PM-MS-0005 v.1.6	LHC Construction/Installation General Coordination Schedule	2003-03-18
LHC-PM-MS-0005 v.1.5	LHC Construction/Installation General Coordination Schedule	2003-03-03
LHC-PM-MS-0005 v.1.4	LHC Construction/Installation General Coordination Schedule	2002-04-19
LHC-PM-MS-0005 v.1.3	LHC Construction/Installation General Coordination Schedule	2002-03-27
LHC-PM-MS-0005 v.1	LEP Dismantling and LHC Construction/Installation General Coordination Schedule	1999-04-06

Hardware commissioning was included

Interconnection non conformities + Inner Triplet Crisis **+7 months**


Courtesy R. Saban

EVM Basics




Industrialization & production ramp-up


LHC superconducting dipole magnets



Schedule Variance



Cost Variance




Risk Analysis

Each risk was assigned a measure for

1. Likelihood rare, possible, likely, frequent, very frequent
 2. Impact on CERN's objectives insignificant, moderate, major, catastrophic
 3. Impact on the interruption of operation hours, days, weeks, months
- from which a score was derived to rank the risks.

A record was prepared for each risk giving a description, the owner, the measure which could be taken to mitigate it, its cost, its score and the new score if the mitigation measures are taken.

Based on this analysis, the Management took the decision on how to handle each risk. i.e. take mitigation measures or accept it.



Courtesy R. Saban

Risk Analysis

[Equipment / System]		Risk Score	
		without consolidation	with consolidation
Probability of failure (P)	Rare (once in 10 to 25 years) = 1 Possible (once in 5 to 10 years) = 2 Likely (once in 2 to 5 years) = 3 Frequent (once a year) = 4	4	2
Impact on CERN's scientific objectives (Io)	Insignificant (loss of 1 day of physics or less) = 1 Moderate (between 1 day and 1 week of physics lost) = 2 Major (up to 1 month of physics lost) = 3 Catastrophic (no more operation, failure to meet scientific objectives for the year) = 5	2	1
Impact on CERN's (AB's) reputation (Ir)	Insignificant = 1 Moderate (problem dealt with inside ATS) = 2 Major (problem discussed at Executive Board or Governing bodies) = 3	2	1
Financial Impact of failure (If)	Insignificant (<0.1% of ATS annual operation budget or less than 100 kCHF) = 1 Moderate (between 0.1% and 1% of ATS annual operation budget or 0.1 – 1 MCHF) = 2 Major (additional budget essential for repair i.e. > 1 MCHF) = 3 Catastrophic (report to Council, could jeopardize CERN's future) = 5	3	1
Safety Impact of failure (Is)	Insignificant (i.e. no injury or environmental consequence) = 1 Moderate (i.e. injury requiring medical attention, but no loss of working days) = 2 Major (i.e. serious injury requiring medical attention and loss of working days) = 3 Catastrophic (i.e. loss of life) = 5	1	1
Facilities Concerned (I)	LHC scientific program (i = 0.3) LHC test beams (i = 0.1) SPS fixed target scientific program (i = 0.15) PS fixed target scientific program (including nTOF) (i = 0.15) AD scientific program (i = 0.15) ISOLDE scientific program (i = 0.15)	0.3	0.3
The Risk score (Rs) is calculated as	$Rs = P \times \max(Io; Ir; If; Is)$		
The weighted Risk score (Rs') is calculated as	$Rs' = Rs \times \sum i$		


Lessons learned

- **Balance risks**: lack of competition for contracts can increase project costs and affect deadlines
- **90 main industrial contracts in the world**
- 2 firms at least for a single adjudication on large/main contracts



From Project to Operation

- LHC has a cycle of ~ 5 years
 - ~ 3 years of operation (incl. 3 TS & YETS)
 - ~ 2 years of Long Shut-down to consolidate, upgrade and perform full maintenance of the different systems.




QAP - document evolution

- Configuration Management


- Exported to the existing beam facilities
- ECRs : templates evolved- additional chapters concerning the existing situation, schedule, impact on utilities and services, safety aspects, follow-up of actions

- Space Reservation Requests were introduced

CERN CH-1211 Geneva 23 Switzerland	EDMS NO. 1551627	REV. 0.2	VALIDITY DRAFT
			
REFERENCE PS-LJ-EC-0001			
Date: 2016-06-20			
SPACE RESERVATION REQUEST			
PS Ring 2 GeV New Injection Septum and Bumper			
Dismantling and removal of the current injection equipment in straight section 42 followed by the installation of the new eddy current septum based injection.			
DOCUMENT PREPARED BY: Michael Hourican TE-ABT	DOCUMENT TO BE CHECKED BY: W. Bartmann, O. Berrig, C. Bertone, M. Bernardini, D. Bodart, J. Borburgh, S. Burger, D. Cotte, J.-M. Cravero, J. Coupard, T. Dobers, G. Dumont, J. Ferreira Somoza, J. Hansen, G. Georgiev, B. Goddard, S. Mataguez, J.-M. Lacroix, P. Lelong, Y. Muttoni, A. Newborough, B. Riffaud, B. Salvant, L. Soby, R. Steerenberg, D. Tommasini + EDMS e-group 'LIU-PS-PROJECT TEAM' + EDMS e-group 'ecr-ps'		DOCUMENT TO BE APPROVED BY: K. Hanke, G. Rumolo, M. Meddahi (on behalf of the LIU Project) R. Losito (on behalf of the IEFC)
DOCUMENT SENT FOR INFORMATION TO: LIU-PS Project team members			
SUMMARY OF THE ACTIONS TO BE UNDERTAKEN: Reservation of space in SS42 of the PS Ring			
<small>Note: When approved, a Space Reservation Request becomes an Space Reservation Decision. This document is uncontrolled when printed. Check the EDMS to verify that this is the correct version before use.</small>			



Configuration & Layout db evolution

Integration of 360° pictures in layout database



Coordination of Programmed Stops

- Participative approach
 - Integration & work preparation meetings **with stakeholders and experts**
WPA: What, where, how, when...safety
 - Skeleton schedule ►
detailed resource levelled schedule
& **access constraints schedule**
 - ALARA meetings where needed
- Non Conformities detection eased with Scans



The painful 1st year of Operation


- 2010 was not a smooth year
 - Operation and physicists waited many years for beams
 - Programmed stops were mandatory to cure the technical teething problems and perform a regular maintenance (reliability)
 - Recovery after each programmed stops was long, coming from the fact that we had no means to strictly control the activities (as the access system was linked only to the “training” database!)
 - Moreover, the same information was copy-paste into different forms, and access time to the machine was huge (average of 20 minutes/person - ~ 500 persons wanting to access - 2 operators granting access)

► Intervention Management Planning And Coordination Tool

IMPACT

- One database grouping all the interventions in all the accelerator complex
- Approval process through the existing Electronic Document Handling (EDH)
- Linked to the Access Control System database
- Generation of safety forms: fire permit, DIMR...

Workflow



71830 - Finished
Created by VIATCHESLAV GRISHIN on 26-Nov-2015 08:48

Save Refresh Clone Split

Approvals

Title*: IP6: HV divider inst @BJBHT.CSL6 Facility: LHC Machine
Responsible: VIATCHESLAV GRISHIN 74131, 163132 Activity Type: Installation
Activity Cluster: Link Priority: Next Technical Stop

What
Where
When
Who
How
Safety
DIMR
Tests
Comments
Work Orders
Info Lines

– Safety Procedures and Hazards



Documents: Document Type: VIC Document number: 2501
Comments:

Lockouts: Document Type: Electrical Document number: 2720


Location Hazards: No Location Hazards declared for the activity

Activity Hazards: Type: None
Comments:
Compensatory Measure list not exhaustive
Compensatory Measures:

From one project to multi-projects



From one project to multi-projects: OPENSE



The screenshot shows the OPENSE website. At the top, the CERN logo and 'Accelerating science' are on the left, and 'Sign in' and 'Directory' are on the right. The main header features the OPENSE logo and the tagline 'an open, lean and participative approach to systems engineering'. Below this is a navigation bar with links: About, Framework, Guidelines & Specifications, Other Resources, Training Material, and Community. A yellow banner with the text 'A common methodology' is overlaid on the top right. The main content area has a section titled 'Why openSE?' with a paragraph explaining the framework's motivation. To the right of this text is a search box and a 'RECENT COMMENTS' section. At the bottom left, there are links for 'What is openSE?' and 'openSE Conceptual Design Report', and a 'Home' link.

CERN Accelerating science


Sign in Directory


 **openSE** | an open, lean and participative approach to systems engineering

[About](#) [Framework](#) [Guidelines & Specifications](#) [Other Resources](#) [Training Material](#) [Community](#)

Why openSE?

The development of this dedicated framework is motivated by the observation that project management and systems engineering standards and methodologies, be they of general purpose such as the **PMI**'s *Project Management Body of Knowledge* or more specialized such as the **NASA**'s *Systems Engineering Handbook*, are not very suited to development projects of scientific facilities emitting ionizing radiations or systems subject to ionized radiations. It should be noted that scientific facilities or systems are importantly one-of-a-kind systems of an extreme complex nature. Project management and systems engineering frameworks designed for space development projects are partly suited, but for reasons that are fully understandable, they insufficiently take into account safety and remote engineering concerns to the extent of their level of requirements for scientific facilities emitting ionizing radiations or systems operating in environments with artificial ionizing radiations.

 [What is openSE?](#)

 [openSE Conceptual Design Report](#)

[Home](#)

Search this site [Search](#)

RECENT COMMENTS

No comments available.

Courtesy: P. Bonnal

From one project to multi-projects: OPENSE


- Common understanding of roles and responsibilities




Courtesy: P. Bonnal

From one project to multi-projects: OPENSE

- Common understanding of a facility or system lifecycle




From one project to multi-projects: OPENSE



From one project to multi-projects

- Frame of a common methodology in place
- Project and management tools in place to manage each project
 - Project structure, regular reviews of technical aspects, cost & schedule
 - Layout db & configuration management
 - Earned Value Management
 - Activity Planning Tool ► short, medium and long term resource planning
 - Schedule & control of activities
- But preparing LS1, we faced to a tricky point:
 - Project engineers were assuming the support resources available
 - Small support requests were coming late
 - Support groups were struggling with the delicate balance between resources and workload




PLAN

Prior to the start of an LS, we need to define which works will be achieved and which are the potential options, based on priorities given to activities and the resources we have

PLAN = A unique repository gathering all activities for a certain period of time with a simple approval process

to harmonize the method to give decision makers and the support group a clear picture of the different requests, and their impacts.

PLAN



PLAN

CERN Accelerating science
Signed in as: foraz
Sign out
Directory

Plan
+ Create Activity
Search for activity ID or title
0 Last activities

LS2
Version 1

Versions
Dashboard
Activity list
Resource list
Specific data
Activity Workflow
Plan Roles
Reports

Activity list *Status: Resource Allocation, Under Approval*

Refresh Table
Reset Filters
Bulk (908)
Export
Show/Hide columns
Search by ID, title...

ID	Title	Group	Priority	WBS	Facilities	Group contribution	Validated contributions	Status
Id	Title	Department...	Select a priority...	Work Breakdown Structure	Facility	Select the contr...	Range	Select a status...
10863	Provide one injection kicker magnet fro ELENA	TE-ABT	4a. Approved project if budgeted	AD	AD	EN-ACE-SU, EN-CV, EN-HE-HH, EN-MME, TE-VSC-BVO	8 of 8	Under Approval
10618	ELENA Phase 1 - installation and commissioning	TE-VSC	4a. Approved project if budgeted	ELENA	AD	BE-ABP-HSC, BE-BI, BE-CO, EN-ACE-SU, EN-MME, TE-MS-C, TE-VSC-ICM	9 of 9	Under Approval
10624	New cryodistribution for AD: 2018	TE-CRG	4a. Approved project if budgeted	AD-UP	AD		0 of 0	Under Approval
10482	Consolidate the ventilation system for the AD target	EN-CV	4a. Approved project if budgeted	AD-CONS	AD	BE-ICS-PCS, EN-EL, EN-HE-HH, HSE-RP, HSE-SEE, SMB-SE	9 of 9	Under Approval
10696	ELENA transfer lines - New project	BE-ICS	4a. Approved project if budgeted	COMPUTING	AD		0 of 0	Under Approval
10610	Consolidation of AD vacuum system [EYETS2016]	TE-VSC	4. Approved projects	AD-CONS	AD	EN-MME	1 of 1	Under Approval
10922	AD C02 RF System Upgrade to Finemet	BE-RF	4a. Approved project if budgeted	AD-CONS	AD	BE-ABP, BE-ABP-HSC, BE-OP, EN-CV, EN-EL, EN-HE-HH, EN-MME, HSE-RP, TE-VSC-BVO	10 of 10	Resource Allocation
10990	Adapt to suppression of ADECONTROLS specific database	BE-CO	4. Approved projects	AD-CONS	AD	BE-OP	1 of 1	Under Approval
10956	General maintenance of AD (unforeseen from now to LS2)	TE-MS-C	4. Approved projects	AD-MO	AD		0 of 0	Under Approval

PLAN v.1.11.9
db-51118.cern.ch
Help
Ask a question
Report an incident

PLAN

Activity 10618 - ELENA Phase 1 - installation and commissioning



General Schedule Resources Comments Documents Data Quality History

Status **Under Approval**

Title

ELENA Phase 1 - installation and commissioning

Type

New

Responsible group

TE-VSC: Vacuum, Surfaces and Coatings Group

Work Breakdown Structure

ELENA - ELENA

Facilities

x AD

Goal

Design, fabrication, installation and commissioning of vacuum chambers.
Commissioning includes all bake-out and acceptance test in situ.

Impact if not done / postponed

delay on ELENA Installation and commissioning

Created On 30-Oct-2015 10:54:04

Created By GERMANA RIDDONE (TE-VSC)

Last Updated On 05-Jul-2016 22:24:20

Last Updated By SYSTEM ADMINISTRATORS

See activity history

See data quality log

Responsible

GERMANA RIDDONE TE-VSC

Priority

4a. Approved project if budgeted

Location Information

Add information on your location...

Refresh

Clone

Workflow Actions

Save

Save and Close

PLAN

Activity 10618 - ELENA Phase 1 - installation and commissioning

General
Schedule
Resources
Comments
Documents
Data Quality
History

Status **Under Approval**

Responsible group

TE-VSC Resources from Responsible Group

1: Preparation

BE-ABP-HSC Impedance and beam ap
BE-BI BPM, SEM, BTV
EN-ACE-SU survey activities
EN-MME eng. design
TE-MSC assembly of vacuum chamber

2: Installation

EN-ACE-SU survey and alignment
TE-MSC magnet installation
TE-VSC-ICM Controls system - Racks

3: Commissioning

BE-CO controls interface

#2724 **EN-MME** Preparation Accepted Periods : 2016 Duration : 3 Months

Description eng. design
Comments from responsible
Comments from contributor Design activities for the ring are competed. Transfer line activities for the moment are frozen: deadline cannot be guaranteed
Contribution periods 2016 (01-01-2016 / 31-12-2016)

Resources

Do you have all the resources?
Is this contribution validated?

Yes
Unknown
No
Yes
No

Personnel - Staff and Fellow

Description	Person (FTE)	Duration	Resource available
Design Office 2016 S2		Weeks	✗

Refresh
Clone
Workflow Actions
Save
Save and Close